TUMKUR DIVISION.

ADVERTISEMENT.

The 29th March 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 25th April 1888, for restoring Kurrihalli Tank, Registered No. 109, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for restoring Kurrihalli Tank, Registered No. 109, Sira Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate of restoring Kurrihalli Tank, Registered No. 109, Sira Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.
Bund—				
Earthwork	C. Yd.	109,598		
New stone work	do	7,367		
Old stone work	do	4,032		
Excavation	do	5,665		
Grade stones	Each.	29		
B. M. stones	do	2		
Total ..				
Sluice No. I—				
Earthwork excavation	C. Yd.	800		
Concrete	C. Ft.	45		
Brick in chunam	do	3,429		
Archwork	do	804		
Chunam plastering	Sq.	24·08		
Covering slabs	S. Ft.	494		
Revetment in steps	C. Yd.	2		
Cutting orifice, &c.	L. S.	5		
Dismantling and clearing old as specified in report.	do	150		
Plug with chain	do	90		
Total ..				
Sluice No. II as per No. I.				
Waste Weir No. II—				
Excavaton	C. Yd.	1,145		
Brick in chunam	C. Ft.	5,139		
Plastering	Sq.	12·75		
Slabs	S. Ft.	310,		

C. T. DALAL,
Executive Engineer.